BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

Modified SCHEDULE - B

Improvements to Roads and Drains at Western side of R K Hegdenagara Cross Road and Surrounding Areas in Ward No.06

SNo	Quantity	Item Name	Unit	Approved Rates of Sri. K S Chowdareddy	
				In figures	In words
1	2575.31	KSRRB 300 - Excavation for road, drains and similar works KSRRB 300-1. Earthwork excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications MORTH (Chapter 2 (P.No.142, I.No.10.1)	Cum	226.02	Rupees Two Hundred Twenty Six And Paise Two Only
2	391.25	KSRRB M2100-10. Providing and laying Plain cement concrete of mix 1:3:6 with OPC @ 220kgs, with crushed 40mm and down size graded granite metal coarse aggregates @0.89cum and fine aggregates @ 0.46cum, in foundation mechanically mixed, placed in foundation and compacted by vibration including curing for 14 days including cost of all materials, labour, HOM curing, form works, scaffolding and centering complete as per specifications. (P.No-222,I No-27.18)	Cum	5692.45	Rupees Five Thousand Six Hundred Ninety Two And Paise Forty Five Only
3	687.96	Providing and laying plain/reinforced cement concrete for side drains using M20 nominal mix concrete with OPC at 300 kgs. With 20mm and sown size granite metal course aggregates at 0.69 cum and fine aggregates at 0.43 cum machine mixed, well compcted for walls and bottom including centring shuttering cost of material HOM of machinary curing etc., complete execluding cost of steel as per MORTH specification no. 1500, 1700, 2200 including cost of material labour HOM complete as per specification. (P.No.271, I.No.37.59.2 of PW, P&IWTD S.R 2018-19)	Cum	7423.00	Rupees Seven Thousand Four Hundred Twenty Three Only
4	48.28	KSRRB - M2300-14: Providing TMT steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, palcing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining memebrs wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications.MORTH Specification No. 1600 & 2200 for TMT bars Fe 500. (P.No.239, I.No.29.29.2 of PW, P&IWTD S.R 2018-19)	MT	77684.45	Rupees Seventy Seven Thousand Six Hundred Eighty Four And Paise Forty Five Only
5	1694.34	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M25 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. (Data Rate)	Sqm	2453.62	Rupees Two Thousand Four Hundred Fifty Three And Paise Sixty Two Only

K. S. Chowdareddy
Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. K S Chowdareddy	
				In figures	In words
6	74.95	Providing and Fixing pre cast covering Slab 250mm thick made out of M25 and jelly 20mm Down size with steel reinforcement including form work,curing,including cost of alll materials, labour,hire charges of machinery, loading, unloading, lead and lift,transportation etc ,complete.As per Engineer incharge. (Data Rate)	Sqm	5688.36	Rupees Five Thousand Six Hundred Eighty Eight And Paise Thirty Six Only
7	38.46	KSRB 4-1.6 ; Providing and laying in position plain cement concrete of Mix 1:2:4 with OPC @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregtes @ 0.53cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM curing complete as per specifications. Specification No. KBS 4.1, 4.2. (P.No.13, I.No.4.6 of PW, P&IWTD SR 2018-19)	Cum	6034.11	Rupees Six Thousand Thirty Four And Paise Eleven Only
8	3980.00	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete. As per the direction of Engineer incharge. (P.No.27, I.No.5.30 of PW, P&IWTD SR 2018-19)	Nos	454.06	Rupees Four Hundred Fifty Four And Paise Six Only
	31.00	Above 125%		454.06	Rupees Four Hundred Fifty Four And Paise Six Only
9	620.50	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications. MORTH Chapter 8 Specification No. KSRRB M800-6. (P.No.180, I.No.24.1 of PW, P&IWTD SR 2018-19)	Sqm	89.03	Rupees Eighty Nine And Paise Three Only
	101.38			89.03	Rupees Eighty Nine And Paise Three Only
10	0.00	KSRRB M200-24. Dismantling of cement concrete pavement by mechanical means using pneumatic tools, breaking to pieces not exceeding 0.02 cum in volume and stock piling at designated locations and disposal of dismantled materials stacking serviceable and unserviceable materials seperately complete as per specifications. Loading and unloading with 8km lead= (I No-18.47,P No-140,KPWD SR 2018-19)	Cum	1021.99	Rupees One Thousand Twenty One And Paise Ninety Nine Only
11	0.00	Construction of granular sub-base Grading-V as Sub-base and drainage layer by providing coarse graded crushed stone aggregates of granite/ trap/basalt material, mixing in a mechanical mix plant at OMC, Carriage of mixed material to work site, spreading in uniform layers with motor grader on prepared surface and compacting with vibratory power roller to achieve the 98 % proctor density, complete as per specifications.(I No-20.5,P No-153,KPWD SR 2018-19)	Cum	2094.47	Rupees Two Thousand Ninety Four And Paise Forty Seven Only

K. S. Chowdareddy

Contractor

Scanned by TapScanner

	Quantity	Item Name	Unit	Approved Rates of Sri. K S Chowdareddy	
				In figures	In words
12	0.00	Constructing un-reinforced, plain cement concrete for pavements using Grade concrete M30 over a prepared base with OPC coarse aggregate at 0.69 cum, fine aggregates at 0.46 cum,Coarse and fine aggregate conforming to IS:383-2016, with Superplastizer at 3 lts conforming to IS 9103-2008. mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). & Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished with floaters in a continuous operation including provision of contraction, expansion, construction and longitudinal joints,including groove cutting charges, joint filler, separation membrane of impermiable plastic sheet of 125 micron, sealant primer, joint sealant, admixtures as approved, curing compound.(P.No-176,I No-22.6.1)	Cum	5470.99	Rupees Five Thousand Four Hundred Seventy And Paise Ninety Nine Only

Executive Engineer
Project Division
Yelahanka Zone
BBMP, Bangalore-92

K.S.Chowdareddy
Contractor

Scanned by TapScanner